

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20478-00-00
Spot: CSWNESW Sec/Twnshp/Rge: 36-9S-22W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: WOLFE Well Number: 1
County: GRAHAM Total Vertical Depth: 3932 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 205 w/150 sxs cmt
Production: Size 5.5 feet: 3931
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/28/2002 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: According to Kansas Corporation Commission Rules & Regulations.
Perforate at 1125' and 1825'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/28/2002 1:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 205' w/150 sxs. 5 1/2" casing at 3931'.
Ran tubing to 2500' - spotted 225 sxs cement with 300# hulls.
Pulled tubing to 1800' - spotted 125 sxs cement with 100# hulls.
Pulled tubing to 950' - circulated with 50 sxs cement and 100# hulls.
Pulled all tubing and topped off with 15 sxs cement.
Tied onto annulus and squeezed 10 sxs cement to Max. P.S.I. 300#.
Total of 425 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
APR 15 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. QUALITY WELL-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses

(TECHNICIAN)

APR 10 2002

WURFIM DRILLING CO. #1 WGLEE 38-9-224
 WICHITA, KANSAS SW NE SW
 CONTR WURFIM DRILLING CTY GRAHAM
 GEOL ROGER WELTY FIELD WC (UNNAMED)
 E 2337 KB CM6/22/71 ^{CARD}ISSUED 7/29/71 IP P 25 BOPD/LANS
 LANS 3555-59

API 15-065-20,478
 LOG TOPS DEPTH DATUM 'G 5/8" 205/150SX

SC	TOPS	DEPTH	DST	DESCRIPTION
SC	1814	+ 523	DST(1)	3551-71/30-30-15-30, 90' OCH,
HLER	3513	-1176		180' HOCH, BHP 964-964#, FP 27-115#
TOR	3536	-1199	DST(2)	3583-3608/30-30-15-15, 5' H/S#
LANS	3554	-1217		OIL, BHP 24-24#, FP 24-24#
BFD	3775	-1438	DST(3)	3622-50/30-30-15-15, 40' SOCM,
MARM	3846	-1509		360' OCM, 120' OCMW, 120' SOCM, BHP
CONG	3902	-1565		568-568#, FP 68-272#
ARB	3909	-1572	DST(4)	3685-3725/30-30-60-30, 240' MO,
LTD	3930	-1593		240' HOCH, 3' OCM, BHP 997-933#, FP
RTD	3932	-1595		56-261#
			DST(5)	3725-60/30-30-60-30, 90' SOCM,
				180' SOCHW, BHP 1008-1008#, FP 27-
				247#

(OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS