

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1968
CONSERVATION DIVISION
Wichita, Kansas
01-15-1968

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-065-2011-00-00

Operator's Full Name Allison & Black,

Complete Address: 1415 Plaza Building, Wichita, Kansas.

Lease Name Schilling Well No. 1

Location SE-SE-NE Sec. 30 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4125

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Woodman-Iannitti Drilling Company,

Address: Box # 387, Hoisington, Kansas. License No. _____

Operation Completed: Hour 1:30 AM Day 12 Month 1 Year 1968

The Above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated with 130 Sx.
Dakota section from 1125' to 1300'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru
DP from 1325' to 1005'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 1/15/68

INV. NO. 7086-u