

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20489-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas
10-04-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Werth Well No. 1

Location NE-SW-NW Sec. 30 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4155'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 7:00 AM Day 25 Month 9 Year 1971

The above well was plugged as follows:

227'--8 5/8" Surface casing, cement circulated. (6 3/4" Hole).
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 70 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 240' and displaced 25 Sx. cement thru DP. from
240' to 165'. Pulled DP, set bridge @ 40' @ 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. D. Fisher
Well Plugging Supervisor

DATE 10/5/71
INV. NO. 4418-W