

Z
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-045-20125-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 29 1968
CONSERVATION DIVISION
Wichita, Kansas
02-29-1968

Operator's Full Name Dean & Clark,

Complete Address: 416 Union Center Building, Wichita, Kansas.

Lease Name Werth Well No. 1

Location NE-NE-SW Sec. 31 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4105'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 11:30AM Day 27 Month 2 Year 1968

The Above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Dakota section from 1000' to 1350'.

Circulated hole with heavy mud. Pulled DP to 1380' and displaced 100 Sx. cement thru
DP from 1380 to 1060'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 2/29/68

INV. NO. 7343-W