

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20643-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1974
01-02-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Incorporated,
Complete Address 300 West Douglas, Wichita, Kansas.
Lease Name Brungardt Well No. J-1
Location NW-SE-NE Sec. 31 Twp. 9 Rge. (E) (W) 25
County Graham Total Depth 3900'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 5:00 PM Day 29 Month 12 Year 1973

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 210 Sx.
Top of Dakota section @ 1100'.
Circulated hole with heavy mud. Pulled DP to 1325' and displaced 110 Cu. Ft. cement
thru DP from 1325' to 1000'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 1/4/74
INV. NO. 8356-W