

15-065-01635-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas
04-04-1972

Operator's Full Name Bankoff Oil Company,

Complete Address 1119 Sherman, Great Bend, Kansas.

Lease Name Brungardt Well No. 1

Location 150' No of CNW-NW Sec. 33 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4055'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor South-West Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30 AM Day 31 Month 3 Year 1972

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.
4045'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to
4034'. Top perforations from 3872' to 3876'.

Pushed plug to 3850', sanded back to 3825' and set 4 sacks cement with dump bailer.
Pulled 4 1/2" casing (3215') and squeezed well initially with 5 sacks hulls and 9 sacks
gel and followed with 110 Cu. Ft. cement from 1275' to 950' then 17 sacks gel from
950' to 270' and followed with 30 Cu. Ft. cement from 270' to 195' then 4 sacks gel
from 195' to 35' and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Max-
imum pump-in pressure--300#. Final shut-in pressure-125#. (Mudding and cementing
operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Pichak
Well Plugging Supervisor

DATE 4-4-72

INV. NO. 5486-W