

KANSAS

ll STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1969

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20288-00-00 12-22-1969

Operator's Full Name Leben-Bankoff,

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Brungardt Well No. 4

Location CS/2-N/2-NW Sec. 33 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 10:00 AM Day 14 Month 12 Year 1969

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12-22-69

INV. NO. 1094-W