

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-30203-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas

04-04-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bankoff Oil Company,

Complete Address 1119 Sherman, Great Bend, Kansas.

Lease Name Brungardt Well No. 2

Location CNE-NW Sec. 33 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4035'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor South-West Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:15 PM Day 31 Month 3 Year 1972

The above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 150 Sx.

3935'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3907'. Top perforations from 3857 to 3861'.

Sanded well back to 3840' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing

(2005') and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed

with 110 Cu. Ft. cement from 1275' to 950' then 18 sacks gel from 950' to 230' and

followed with 30 Cu. Ft. cement from 230' to 155' then 3 sacks gel from 155' to 35'

and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Maximum pump-in pressure

--250#. Final shut-in pressure--75#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. G. Nichols
Well Plugging Supervisor

DATE 4-4-72

INV. NO. 5487-W