

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 12 1961

CONSERVATION DIVISION  
Wichita, Kansas

12-12-1961

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-065-03504-00-00

File No. \_\_\_\_\_ County: Graham

Location: CSW SE Sec. 36 Twp. 9 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 25

Name of Field: \_\_\_\_\_ Total Depth: 4055

I have this date completed supervision of plugging of:

Lease Name: Richmeier Well No. 1

Operator's Full Name: J. A. Terteling & Sons

Complete Address: 320 Petroleum Bldg Denver, Colo

Plugging Contractor Kimbark Exploration Co

Address: Denver, Colo License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11PM Day 6 Month 12 Year 61

The above well was plugged as follows:

8 5/8" 195' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 550', displaced

20 sax cement through drill pipe, heavy mud to 190', set plug and 20

sax cement at 190', heavy mud to 35', set plug, 1/2 sack hulls and filled to

bottom cellar with cement.

Signed: Edon Petty

Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED

DATE 12/27/61

INV. NO. 4227-W