

KANSAS

el STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1971

CONSERVATION DIVISION
Wichita, Kansas

03-25-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20 422-00-00

Operator's Full Name Thunderbird Drilling and Beacon Resources,

Complete Address P. O. Box #18407, Wichita, Kansas.

Lease Name Clark Well No. B-1

Location SE-NE-NE Sec. 36 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4110'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 6:15 AM Day 23 Month 3 Year 1971

The above well was plugged as follows:

256'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1025'.

Circulated-hole with heavy mud.--Pulled-DP to 1250' and displaced 100-Sx. cement thru
DP from 1250' to 925'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200' Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *R. L. Nichols*
Well Plugging Supervisor

DATE 3/25/71
INV. NO. 3457-W