

15-065-00652-00-00

KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION

SEP 19 1961 09-19-1961 CONSERVATION DIVISION Wichita, Kansas

TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

File No. \_\_\_\_\_ County: Graham  
Location: CNW SE Sec. 30 Twp. 9 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 25  
Name of Field: \_\_\_\_\_ Total Depth: 4400

I have this date completed supervision of plugging of:

Lease Name: Richmeier Well No. 1

Operator's Full Name: Imperial Oil Co

Complete Address: 780 4th Natl Bk Wichita, Kansas

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 15 Month 9 Year 61

The above well was plugged as follows:

<sup>189'</sup>  
8 5/8" ~~3 1/2~~' circulated with cement - 4 1/2" at 4083' with 100 sax cement perforated 4038' - filled with sand to 400', set 3 sax cement with dump b bailer - pulled 3500', 4 1/2" to 550', circulated hole with mud through 4 1/2" at 550' ( 16 sax Gel), displaced 20 sax cement through 4 1/2" at 550', heavy mud to 170', displaced 20 sax cement through 4 1/2" at 170', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 9/28/61  
INV. NO. 3466-w