

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20278-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1971
CONSERVATION DIVISION
Wichita, Kansas
03-18-1971

Operator's Full Name NIXON R. P. Nixon Operations, Incorporated,

Complete Address Box-#589, Russell, Kansas.

Lease Name Mills Well No. 1

Location CNW-SE Sec. 4 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4030'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 4:00 PM Day 15 Month 3 Year 1971

The above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru
DP from 1375' to 1050'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 3/18/71
INV. NO. 3427-W