

15-179-30000-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1965
02-10-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Incorporated,
Complete Address: 410 4th National Bank Building, Wichita, Kansas.
Lease Name Minium Well No. 1
Location CNW-NW Sec. 4 Twp. 9 Rge. (E) (W) 26
County Sheridan Total Depth 4010
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: Well produced an indeterminate amount of oil.
Plugging Contractor: Bert Self Casing Pulling Company,
Address: R. R. #4, Hutchinson, Kansas License No. 48
Operation Completed: Hour 12:30PM Day 4 Month 2 Year 1965

The Above well was plugged as follows:

228' -- 8 5/8" Surface pipe, cement circulated with 200 Sx.
3985' -- 5 1/2" Production casing cemented with 150 Sx.

Sanded well back to 3960' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing to 600' and circulated heavy gel mud. (used 17 Sx. gel)
Pulled 5 1/2" to 540' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to
210' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 30'
and 10 Sx. cement to bottom of cellar. (Recovered 2300' 5 1/2" Casing).

(Mudding and cementing operations performed by Halliburton)

I hereby certify that the above well was plugged as herein stated.

DATE 2/10/65
INV. NO. 663-11

Signed: W. L. Nichols
Well Plugging Supervisor