

15-179-20277-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
02-12-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rosen Oil Corporation,

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Minium Well No. 1

Location SE-SE-NE Sec. 5 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 3980'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Kansas License No.       

Operation Completed: Hour 7:00 AM Day 9 Month 2 Year 1971

The above well was plugged as follows:

238'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru  
DP from 1225' to 900'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from 245'  
to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. S. Nichols  
Well Plugging Supervisor

DATE 2/12/71

INV. NO. 3334-4