

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20234-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas
10-21-1969

Operator's Full Name Theodore Gore,
Complete Address 650 Fourth National Bank Building, Wichita, Kansas.
Lease Name Popp Well No. 1
Location SW-SE-SW Sec. 6 Twp. 9 Rge. (E) (W) 26
County Sheridan Total Depth 3970'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Leben Drilling, Incorporated,
Address Box #486, Great Bend, Kansas. License No.
Operation Completed: Hour 4:00 PM Day 19 Month 10 Year 1969

The above well was plugged as follows:

271'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from
270' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 10/21/69
INV. NO. 696-W