

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20384-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1974
05-13-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated & P-S Petroleum Company,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Popp Well No. 1

Location CS/2-SW_SW Sec. 6 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4015'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 2:00 PM Day 10 Month 5 Year 1974

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/15/74
INV. NO. 9111-W