



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-779-20277-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1971
CONSERVATION DIVISION
Wichita, Kansas
02-12-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Corporation,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Minium Well No. 1

Location: SE-SE-NE Sec. 5 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 3980 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Shawn was instructed to plug the well as follows:

238'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Dichel
Conservation Division Agent