



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-179-20234-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas

10-21-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore.

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Popp Well No. 1

Location: SW-SE-SW Sec. 6 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 3970' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

271'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent