

State of Kansas



15-179-20384-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION MAY 13 1974 15-13-1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc. & P-S Petroleum Co.,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Popp Well No. 1

Location: CS/2-SW-SW Sec. 6 Twp. 9 Rge. (E)(W)26

County: Sheridan Total Depth 4015' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

249'--8 5/8" Surface casing, cement circulated with 160 Sx. Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 250' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols

Conservation Division Agent