

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1967

05-31-1967

CONSERVATION DIVISION
Wichita, Kansas

15-179-20015-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: L. J. Dreiling & Sons, Incorporated,

Complete Address: Victoria, Kansas.

Lease Name: Minium Well No. 1

Location: CE/2-NE Sec. 19 Twp. 9 Rge. (E)(W) 26

County Sheridan Total Depth 4000 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

179'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

" " 180' with 1/4 sk. hulls & 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent