



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-179-20105-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1968
CONSERVATION DIVISION
Wichita, Kansas
06-04-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Allison & Bland and Abercrombie Drilling, Inc.

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Friend Well No. 1

Location: NE-NW-SE Sec. 19 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 3840 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

259'---7 5/8" OD Surface pipe, cement circulated with 125 Sx. (6 3/4" Hole). Dakota section top @ 960'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 80 Sx. cement thru DP. Pull DP to 275' and displace 15 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Mitchell
Conservation Division Agent