

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1967
11-13-1967
CONSERVATION DIVISION
Wichita, Kansas

15-179-20056-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michaels of Sage Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: 400 No. Woodlawn, Suite #7, Wichita, Kansas.

Lease Name: Chestnut Well No. 1

Location: Appr. NE-NE-SW Sec. 22 Twp. 9 Rge. (E)(W) 26

County Sheridan Total Depth 4157' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Michaels was instructed to plug the well as follows:

2 1/2" -- 8 5/8" Surface pipe, cement circulated with 165 Sx.
Dakota section from 1130' to 1305'.

Circulate hole with heavy mud. Pull DP to 1330' and displace 100 Sx.
cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent