



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1973  
08-16-1973  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-20360-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Company has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Co., Inc., & Bill J. Porter,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Fore Well No. 1

Location: CNE-SE Sec. 25 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4115' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 110 Cu. Ft.  
cement thru DP from 1125' to 800'. Pull DP to 245' and displace 30 Cu. Ft.  
cement thru DP from 245' to 170'. Pull DP, set bridge @ 40' with 1/2 sack  
hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent