

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CORPORATION COMMISSION
NOV 6 1967
11-06-1967
CONSERVATION DIVISION
Wichita, Kansas

15-179-20054-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michaels of Sage Drlg. Co. Inc., has this date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: 400 No. Woodlawn, Suite #7, Wichita, Kansas.

Lease Name: Breeden Well No. 1

Location: App. NE-NE-SW Sec. 28 Twp. 9 Rge. (E)(W) 26

County Sheridan Total Depth 1125 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michaels was instructed to plug the well as follows:

247'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1275' to 1100'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack bulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

[Signature]
Conservation Division Agent