



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20272-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1970
CONSERVATION DIVISION
Wichita, Kansas

10-20-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Dunne-Gardner Petroleum, Incorporated,

Complete Address: 200 West Douglas, Wichita, Kansas.

Lease Name: Friend Well No. 1

Location: NE-NE-SW Sec. 29 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4025' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

266'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1240' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

R. L. Nichols
Conservation Division Agent