



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20182-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 17 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 02-17-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name: Farmer Well No. B-1

Location: CSE-SE Sec. 3 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4175' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

257'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1435' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Fickels
 Conservation Division Agent