

State of Kansas



15-179-20082-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
04-01-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Graves Drilling Company,

Complete Address: 505 Union Center Building, Wichita, Kansas.

Lease Name: Pratt Well No. 1

Location: SE-SE-SE Sec. 4 Twp. 9 Rge. (E)(W) 28

County Sheridan Total Depth 4135 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

242'--8 5/8" Surface pipe, cement circulated with 180 Sx.  
Top of Dakota section @ 1150'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 100 Sx.  
cement thru DP, Pull DP to 270' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

Conservation Division Agent