



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1973
09-17-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20364-00-00

Dear Sir:

Mr. Weber of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Geo. A. Reed

Complete Address: 1223 Union Nat'l Bldg., Wichita, Ks.

Lease Name: Farber Well No. 1

Location: SW NW NE Sec. 4 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4055' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weber was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1250' and displace

70 sk cmt thru drill pipe. Heavy mud to 250' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Wenzel
Conservation Division Agent