



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1972  
12-27-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20340-00-00

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well;

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Petroleum Reserves,

Complete Address: Oklahoma City, Oklahoma.

Lease Name: Billinger Well No. 1

Location: CNW-SE Sec. 9 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4100' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1175'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Oschuls  
Conservation Division Agent