

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-179-20,902 -00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Walter A. Ohmart, Jr. OPERATORS LICENSE NO. 3448

ADDRESS 1580 Lincoln St, Suite 1180, Denver, CO 80203 PHONE # (303) 830-0197

LEASE (FARM) Kennedy WELL NO. 1-15 WELL LOCATION NW-NE-SW COUNTY Sheridan

SEC. 15 TWP. 9S RGE. 28 ~~XXXX~~ (W) TOTAL DEPTH 4200 PLUG BACK TO

Check One:

OIL WELL  GAS WELL  D & A X SWD or INJ WELL  DOCKET NO.

SURFACE CASING SIZE 8-5/8 SET AT 276 CEMENTED WITH 200 SACKS

CASING SIZE  SET AT  CEMENTED WITH  SACKS

PERFORATED AT

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug at 2450' w/25 sx; 2nd plug at 1500'  
w/100 sx; 3rd plug at 325' w/40 sx; 4th plug at 40' w/10 sx and wiper plug. 15 sx in rathole  
10 sx in mousehole. All cement, 6% gel, 3% Ca Cl.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? No  
(If not, explain) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11:00 a.m. 8-11-87

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Craig PHONE # (913) 674-2876

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack H. Wharton  
(Operator or Agent)

RECEIVED  
AUG 17 1987  
08-17-1987  
CONSERVATION DIVISION  
Wichita, Kansas

Aug 24, 1986