

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-179-21,070-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ABERCROMBIE DRILLING, INC. KCC LICENSE # 5422
(owner/company name) (operator's)

ADDRESS 150 N. MAIN, SUITE 801 CITY WICHITA

STATE KANSAS ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE LEIKER 'A' WELL# 1 SEC. 27 T. 9S R. 28 (East/West)

- E/2 - NE - SPOT LOCATION/QQQQ COUNTY WICHITA

1320' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

660' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 13 3/8" SET AT 249.07' CEMENTED WITH 60-40 posmix - 225 sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2766' / 2771' T.D. 4175' PBD _____ ANHYDRITE DEPTH _____
(G.L./K.E.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set 1st plug @ 2400' w/25 sx; 2nd plug @ 1450' w/100sx;

3rd plug @ 300' w/40 sx; solid bridge at 40' w/10 sx; rathole 15 sx; total 190 sx

60-40 posmix 6% gel 3% cc, 1/4# Floseal per sk.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACC-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH THE S.S. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin

CONSERVATION DIVISION (913) 743-5443
Wichita, Kansas

ADDRESS 533 N. Main City/State Wameeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (if known?) Complete at 5:00 a.m. 6-3-94.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-116) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: _____ AUTHORIZED OPERATOR/AGENT: Tony Martin
(signature)