



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1969
CONSERVATION DIVISION
Wichita, Kansas
04-17-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20195-00-00

Operator's Full Name Glen Rupe and American Drilling Company.

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name Ochs Well No. B-1

Location NW-SW-SE Sec. 13 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 1170'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: American Drilling Company, Incorporated.

Address: Sutton Place, Wichita, Kansas. License No. _____

Operation Completed: Hour 10:00PM Day 12 Month 4 Year 1969

The Above well was plugged as follows:

241'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from
270' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/17/69
INV. NO. 9614-W

Signed: [Signature]
Well Plugging Supervisor