

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas
07-14-1969

15-179-20215-00-00

Operator's Full Name Donald C. Slawson.

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Ochs Well No. F-1

Location SE-SE-NE Sec. 13 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4064

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated.

Address 408 One-Twenty Bldg., Wichita, Ks. License No.

Operation Completed: Hour 12:00 M Day 6 Month 7 Year 1969

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru
DP from 1400' to 1075'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/14/69

INV. NO. 93-W

Signed: M. S. Nichols
Well Plugging Supervisor