

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20266-00-00

09-02-1970

Operator's Full Name Dreiling and Hiko Bell Mining & Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Ochs Well No. 3

Location NW-NW-SW Sec. 13 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4155'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 2:00 PM Day 29 Month 8 Year 1970

The above well was plugged as follows:

274'-8 5/8" Surface casing cement circulated w/175 Sx.

Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 100 Sx. cement thru

DP from 1450' to 1125'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from

310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 9/2/70

INV. NO. 2472-W