

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1973
CONSERVATION DIVISION
Wichita, Kansas
03-05-1973

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20324-00-00

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Ochs Well No. 4
Location SW-SW-SW Sec. 13 Twp. 9 Rge. (E) (W) 28
County Sheridan Total Depth 4140'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 11:45 AM Day 28 Month 2 Year 1973

The above well was plugged as follows:

293'--8 5/8" Surface casing cement circulated.
This well was drilled as a rotary hole and temporarily abandoned about 9/5/72.
Squeezed well initially with 5 sacks hulls and 9 sacks gel and followed with 110 Cu.
Ft. cement from 1475' to 1150', then 21 sacks gel from 1150' to 300' and followed
with 30 Cu. Ft. cement from 300' to 225' then 5 sacks gel from 225' to 25' and
finally 10 Cu. Ft. cement from 25' to bottom of cellar. (Mudding and cementing op-
erations by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/5/73
INV. NO. 7099-W

Signed: W. L. Nichols
Well Plugging Supervisor