

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-179-30005-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 - 1965
08-05-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Alex Well No. 1

Location CSE-SW Sec. 14 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4695

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 12:00M Day 1 Month 8 Year 1965

The Above well was plugged as follows:

240'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 250', set plug with 1/2 sack hulls and

displaced 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2

sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 8/5/65

INV. NO. 1576-W

Signed: W. D. Nichols
Well Plugging Supervisor