

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

10-31-1968
RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20154-00-00

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address: 1125 Wichita Plaza Building,

Lease Name Pratt Well No. 1

Location App. NE-NE-NE Sec. 16 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 1155

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 9:00 AM Day 29 Month 10 Year 1968

The Above well was plugged as follows:

229'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 1125'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

Signed: W. B. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/31/68
INV. NO. 8729-4