

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20089-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
04-29-1968

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Dunham & Goeckler Well No. 1

Location NW-NW-SW Sec. 22 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4200

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 2:30 AM Day 21 Month 4 Year 1968

The Above well was plugged as follows:

224'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 100 Sx. cement thru  
DP from 1450' to 1125'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. S. Nichols  
Well Plugging Supervisor

INVOICED

DATE 4/29/68  
INV. NO. 7648-u