

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

SEP 17 1973
09-17-1973
CONSERVATION DIVISION
Wichita, Kansas

15-179 - 20363-00-00

Operator's Full Name G. N. Rupe

Complete Address 925 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Miller Well No. 1

Location NE NW SW Sec. 26 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4146'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Chief Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 10:45 A Day 14 Month 9 Year 1973

The above well was plugged as follows:

RTD 4146' 8 5/8 csg set at 222' cwc: 160 sk. Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 1200' and displaced 70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 9-17-73

INV. NO. 7914-W