

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1974
04-29-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20375-00-00

Operator's Full Name John O. Farmer, Incorporated.

Complete Address Box #352, Russell, Kansas.

Lease Name Reitcheck Well No. 1

Location NE-NE-NE Sec. 4 Twp. 9 Rge. (E) (W)29

County Sheridan Total Depth 4200'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:15 AM Day 24 Month 4 Year 1974

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 165'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 110 Cu. Ft. cement
thru DP from 1400' to 1075'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dickels
Well Plugging Supervisor

DATE 5/1/74

INV. NO. 9018-W