

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20133-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1968
CONSERVATION DIVISION
Wichita, Kansas
09-18-1968

Operator's Full Name Koch Exploration Company,

Complete Address: Box #2256, Wichita, Kansas.

Lease Name Patmon Well No. 1

Location SE-NE-SW Sec. 5 Twp. 9 Rge. (E) (W) 29

County Sheridan Total Depth 4230'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 2:00 AM Day 16 Month 9 Year 1968

The Above well was plugged as follows:

231'--8 5/8" Surface casing, cement circulated with 210 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 825'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Dichek
Well Plugging Supervisor

DATE 9/18/68
INV. NO. 8477-W