

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1968
CONSERVATION DIVISION
Wichita, Kansas
06-10-1968

15-179-20107-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rock Island Oil And Refining Company,

Complete Address: 321 West Douglas, Wichita, Kansas.

Lease Name Johnson Well No. B-1

Location SE-SE-SE Sec. 8 Twp. 9 Rge. (E) (W) 29

County Sheridan Total Depth 4195

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Ks. License No.

Operation Completed: Hour 3:00PM Day 8 Month 6 Year 1968

The Above well was plugged as follows:

258'--8 5/8" Surface pipe, cement circulated.
Top of Dakota section @ 1300'.

Circulated-hole-with-heavy-mud. -Pulled DP-to-1525' and-displaced-100-Sx.-cement thru
DP from 1525 to 1200'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6/10/68
INV. NO. 1920-w