

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

NOV 9 1970

CONSERVATION DIVISION
Wichita, Kansas

11-09-1970

15-179-20275-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Sloan Well No. 1

Location CS/2-SW-NE Sec. 8 Twp. 9 Rge. (E) (W) 29

County Sheridan Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 8:45 PM Day 4 Month 11 Year 1970

The above well was plugged as follows:

252'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from
270' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. S. Nichols
Well Plugging Supervisor

DATE 11/9/70

INV. NO. 2822-W