

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-179-30006-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1965
08-18-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Pratt Well No. D-1

Location CSW-SW Sec. 14 Twp. 9 Rge. (E) (W) 29

County Sheridan Total Depth 4615

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:00Am Day 14 Month 8n Year 1965

The Above well was plugged as follows:

170'--8 5/8" Surface casing cement circulated with 160 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.

cement thru DP. Heavy mud to 160', set plug with 1/2 sack hulls and

displaced 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2

sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 8/18/65
INV. NO. 1649-W