

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1968
CONSERVATION DIVISION
Wichita, Kansas
09-06-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20131-00-00

Operator's Full Name Koch Exploration Company,

Complete Address: Box #2256, Wichita, Kansas.

Lease Name Bange Well No. 1

Location SW-NE-NW Sec. 17 Twp. 9 Rge. (E) (W) 29

County Sheridan Total Depth 2550

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert & Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 7:00AM Day 3 Month 9 Year 1968

The Above well was plugged as follows:

264'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1180' and displaced 100 Sx. cement thru
DP from 1180' to 790'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from 275'
to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. R. Nichols
Well Plugging Supervisor

INVOICED

DATE 9/6/68
INV. NO. 8412-11