

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sheridan County, Sec. 8 Twp. 9S Rge. (E) 28 (W)

Location as "NE/CNW/SW" or footage from lines C NW SW

Lease Owner Imperial Oil Co.

Lease Name Mosier "A" Well No. 1

Office Address 780 Fourth National Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 15 19 68

Application for plugging filed May 15 19 68

Application for plugging approved May 15 19 68

Plugging commenced May 15 19 68

Plugging completed May 15 19 68

Reason for abandonment of well or producing formation No commercial quantities of oil and/or gas were encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4160 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface casing - 8	5/8"	at	233'		Not pulled.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4160 feet to feet for each plug set.

Set 1st plug at 2200 ft. with 100 sacks of cement.
Set 2nd plug at 210 ft. with 20 sacks of cement.
Set 3rd plug at 40 ft. with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1968
CONSERVATION DIVISION
Wichita, Kansas
05-27-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil Company
Address 780 Fourth National Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Charley V. Shank


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL COMPANY

(Signature) Charley V. Shank
Charley V. Shank
780 Fourth National Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 68

My commission expires March 3, 1970

Mary J. Brown
Notary Public.



DRILLER'S LOG

15-179-20097-00-00

Imperial Oil Company
780 Fourth National Bldg.
Wichita, Kansas 67202

Mosier "A" No. 1
C NW SW Section 8-9S-28W
Sheridan County, Kansas

Total Depth: 4160 ft.

Elevation: 2793 K.B.

Commenced: 5-5-68

Completed: 5-15-68
Dry Hole

Contractor: Imperial Oil Company, Rig #2

Casing Record: Set 8 5/8" surface casing at 233 feet with 185 sacks of cement.

Figures indicate bottom of formations:

Sample Tops

233' Sand-shale		
380' Shale	Anhydrite	2407 (+ 386)
2073' Shale-shells	Base Anhydrite	2442 (+ 351)
2200' Dakota Sand	Elmont	3570 (- 777)
2400' Shale	Howard	3609 (- 816)
2407' Shale-lime	Topeka	3659 (- 866)
2442' Anhydrite	Heebner	3876 (-1083)
2585' Lime-shale	Toronto	3898 (-1105)
2940' Shale-lime	Lansing	3912 (-1119)
3031' Lime-shale	Base Kansas City	4150 (-1357)
3325' Shale-lime	Rotary Total Depth	4160 (-1367)
3530' Lime-shale		
3578' Shale-lime		
3960' Lime-shale		
4086' Lime		
4137' Lime-shale		
4160' Lime		
<u>4160' Rotary Total Depth</u>		


RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1968
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Charley V. Shank
Charley V. Shank

Subscribed and sworn to before me this 17th day of May, 1968.



My Commission Expires:
March 3, 1970

Mary J. Brown
Mary J. Brown, Notary Public