

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sheridan County, Sec. 9 Twp. 9S Rge. (E) 28 (W)

Location as "NE/CNW%SW%" or footage from lines C SW SW

Lease Owner Imperial Oil Company

Lease Name Pratt Well No. 1

Office Address 780 Fourth National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-25-1968

Application for plugging filed May 24 1968

Application for plugging approved May 24 1968

Plugging commenced May 24 1968

Plugging completed May 25 1968

Reason for abandonment of well or producing formation No commercial quantities of oil and/or gas were encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4140 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface casing at	209 ft.		8 5/8"		Not pulled

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1968
CONSERVATION DIVISION
Wichita, Kansas
6/6-68-1968

Describe in detail the manner in which the well was plugged, indicating where the mud was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of each and depth placed, from 4140 feet to feet for each plug set.

Set first plug at 2200 feet with 100 sacks cement.
Set second plug at 200 feet with 125 sacks cement.
Set thrid plug at 40 feet with 10 sacks cement.

Name of Plugging Contractor Imperial Oil Company
Address 780 Fourth National Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. William A. Sladek


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William A. Sladek
IMPERIAL OIL COMPANY
780 Fourth National Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of June, 1968

My commission expires March 3, 1970

Mary J. Brown
Notary Public.



DRILLER'S LOG

15-179 - 20103 - 00-00

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

Pratt No. 1
C SW SW Sec. 9-9S-28W
Sheridan County, Kansas

Total Depth: 4140 feet

Elevation: 2772 K.B.

Commenced: 5-15-68

Completed: 5-25-68
Dry Hole

Contractor: Imperial Oil Company, Rig #2

Casing Record: Set 8 5/8" surface casing at 209 feet with 185 sacks cement.

Figures indicate bottom of formations:

44' Clay
209' Rock-sand
638' Shale
840' Shale-shells
1770' Shale-sand
2110' Shale-shells
2392' Lime-shale
2428' Anhydrite
2600' Shale-shells
2830' Shale-lime
3585' Lime-shale
3645' Lime
3855' Lime-shale
4140' Lime
4140' Rotary Total Depth

Sample Tops

Anhydrite 2392 (f 380)
Base Anhydrite 2428 (f 344)
Elmont 3563 (- 791)
Howard 3604 (- 832)
Topeka 3655 (- 883)
Heebner 3864 (-1092)
Toronto 3890 (-1118)
Lansing 3901 (-1129)
Rotary Total Depth 4140 (-1368)

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1968
CONSERVATION DIVISION
Wichita, Kansas
06-06-1968

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By William A. Sladek
William A. Sladek

Subscribed and sworn to before me this 5th day of June, 1968.

Mary J. Brown
Mary J. Brown, Notary Public

My Commission Expires:
March 3, 1970

