

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD 15-179-20614-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Sheridan SEC. 10 TWP. 9S RGE. 28W E/W
 Location as in quarters or footage from lines:
NE SW SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner K & E Petroleum Corp.
 Lease Name WEEKS Well No. 1
 Office Address 300 Hardage Center, Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed September 24, 1981
 Application for plugging filed September 24, 1981
 Plugging commenced September 24, 1981
 Plugging completed September 24, 1981
 Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
 Producing formation _____ Depth to top _____ bottom T.D. 4160'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 1260' with 70 sx.
Set 2nd plug @ 270' with 40 sx.
Set 3rd plug @ 40' with 10 sx.
5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c.
Plug was down @ 4:30 a.m., 9/24/81.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Cntr., Wichita, KS 67202
 (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry
 Elizabeth G. Terry Notary Public
 RECEIVED
 STATE CORPORATION COMMISSION
 OCT 8 1981
 10-08-1981
 CONSERVATION DIVISION
 Wichita, Kansas



15-179-20614-00-00

CONTRACTORS WELL LOG

OPERATOR: K & E Petroleum Corp.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: WEEKS #1
 LOCATION: NE SW SE, Sec. 10-9S-28W
 Sheridan County, Kansas
 SPUD DATE: 9/17/81
 COMPLETION DATE: 9/24/81

0	288	Sand & Shale
288	2390	Shale
2390	2421	Anhydrite
2421	3115	Shale
3115	3543	Shale & Lime
3543	3813	Lime & Shale
3113	4160	Lime
	4160	Rotary Total Depth

Spud hole @ 10:30 a.m., 9/17/81. Drilled 288' of a 12 1/4" hole. Ran 7 jts. of 8 5/8" 20# casing (tally 278.49) set @ 286.49' and cemented with 200 sx. Common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 4:30 p.m., 9/17/81.

4160 TD. Set 1st plug @ 1260' with 70 sx. Set 2nd plug @ 270' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c. Plug was down @ 4:30 a.m., 9/24/81.

SAMPLE TOPS:

Anhydrite 2390'
 B/Anhydrite 2421'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WEEKS #1, NE SW SE, Sec. 10-9S-28W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 5th day of October, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION

OCT 8 1981
 10-8-1981
 CONSERVATION DIVISION
 Wichita, Kansas

