

15-179-20532-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County, Sec. 11 Twp. 9S Rge. 30WE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE SE

Lease Owner Voyager Petroleum, Inc. -Godsey-Earlough

Lease Name Hornberger Well No. 1

Office Address 6600 So. Yale, Tulsa, Oklahoma 74136

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed March 17 19 79

Application for plugging filed (verbally) March 17 19 79

Application for plugging approved (verbally) March 17 19 79

Plugging commenced March 17 19 79

Plugging completed March 17 19 79

Reason for abandonment of well or producing formation

No commercial quantity of oil or gas encountered.

If a producing well is abandoned, date of last production


19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation Depth to top Bottom Total Depth of Well 4580'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 4580'

Set 1st plug at 1300' with 70 sacks

2nd plug at 240' with 20 sacks

3rd plug at 40' solid bridge with 10 sacks

rathole with 5 sacks.

Cemented with 50/50 posmix, 6% gel.

Plug was down at 3:15 p.m., 3-17-79.

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1979
03-23-1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature)

Jack L. Partridge

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 79

Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR: Voyager Petroleum, Inc.
 Godsey-Earlougher Division
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Hornberger #1
 LOCATION: C NE SE, Section 11-9S-30W
 Sheridan County, Kansas
 SPUD DATE: March 08, 1979
 COMPLETION DATE: March 17, 1979

| | | |
|------|------|----------------------|
| 0 | 256 | Clay, sand and shale |
| 256 | 2054 | Shale and sand |
| 2054 | 2509 | Shale |
| 2509 | 2544 | Anhydrite |
| 2544 | 2816 | Shale |
| 2816 | 3445 | Shale and lime |
| 3445 | 3788 | Lime and shale |
| 3788 | 4580 | Lime |
| | 4580 | Rotary Total Depth |

Spud hole at 5:30 p.m., March 08, 1979. Drilled 256' of 12 1/4" hole. Ran 6 joints of 8-5/8" casing. Set at 255' rotary bushing with 200 sacks of regular cement, 3% Ca.Cl. Cement in cellar. Plug was down at 1:30 a.m., March 09, 1979.

T.D. 4580'. Set 1st plug at 1300' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 3:15 p.m., March 17, 1979.

SAMPLE TOPS:

Anhydrite 2509'
 B/Anhydrite 2544'

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 23 1979
 03-23-1979
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Hornberger #1, C NE SE, Section 11-9S-30W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 21st day of March, 1979.

 Sherrie Brooks, Notary Public

My commission expires 8-21-82.