


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-179-00187-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

SHERIDAN County. Sec. 12 Twp. 9 Rge. (E) 30 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner EMPIRE DRILLING COMPANY
Lease Name BAALMAN Well No. 1
Office Address 400 BROWN BUILDING WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 7-8-57 19__
Application for plugging filed 7-8-57 19__
Application for plugging approved 7-8-57 19__
Plugging commenced 7-8-57 19__
Plugging completed 7-8-57 19__
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4563 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>SURFACE</u>		<u>0</u>	<u>251'</u>	<u>8 5/8"</u>	<u>2510</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

SET BOTTOM PLUG 245' 1/2 SACK HULLS 20 SACKS CEMENT
SET SECOND PLUG 40' 1/2 SACK HULLS 10 SACKS CEMENT TO TOP

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 400 BROWN BUILDING WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, THEODORE GORE (employer of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore

400 BROWN BUILDING
(Address)

SUBSCRIBED AND SWORN TO before me this 15TH day of JULY, 19 57

My commission expires JULY 2, 1958

Hazel Pierson
HAZEL PIERSON Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1957
07-19-1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 12 T 9 R 30W
BOOK PAGE 27 LINE 10



COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

FARM: BAALMAN NO 1

LOCATION: NE NE NE SEC 12-9-30W SHERIDAN COUNTY, KANSAS

COMMENCED: JUNE 26, 1957

ELEVATION: 2893 KB

COMPLETED: JULY 8, 1957

0	TO	1525	SHALE AND SAND
1525	TO	2510	SHALE AND SHELLS
2510	TO	2524	SHALE
2524	TO	2561	ANHYDRITE
2561	TO	3100	SHALE AND SHELLS
3100	TO	3530	SHALE AND LIME
3530	TO	3615	LIME AND SHALE
3615	TO	3750	SHALE AND SHELLS
3750	TO	3970	LIME AND SHALE
3970	TO	4035	SHALE AND LIME
4035	TO	4292	LIME
4292	TO	4340	SHALE AND LIME
4340	TO	4500	SHALE
4500	TO	4545	SHALE AND LIME
4545	TO	4563	CHERT
		4563	RTD
			D & A

SET: 8 5/8" 251' WITH 135 SACKS CEMENT

TOPS:	ANHYDRITE	2524
	HEEBNER	3946
	TORONTO	3969
	LANSING KANSAS CITY	3984
	BASE KANSAS CITY	4228
	MISSISSIPPIAN	4513

I, THEODORE GORE, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE BAALMAN NO 1 NE NE NE SEC 12-9-30, SHERIDAN COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Theodore Gore

 THEODORE GORE

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 15TH DAY OF JULY, 1957.

Hazel Pierson

 HAZEL PIERSON, NOTARY PUBLIC

MY COMMISSION EXPIRES JULY 2, 1958

RECEIVED
 STATE OF KANSAS DIVISION

JUL 17 1957

CONSERVATION DIVISION
 Wichita, Kansas

07-17-1957

PLUGGING
 FILE SEC 12-9-30W
 BOOK PAGE 27 LINE 10